

Five Steps To...



...Successful Ecological Restoration of Mangroves



this manual was put together mostly in the wee hours of night by
friends of the mangrove

methodology: Robin Lewis - Lewis Environmental Services

design & layout: Ben Brown

text: Ben Brown

illustrations: Ibnu, PA Tri Priyanto, Rappy, Ben Brown & selected

graphics from the KUILU CD-Rom by CUSO

editors: R.R. Lewis, Alfredo Quarto, Jim Enright, Elaine Corets,
Jurgenne Primavera, PhD. T. Ravishankar, PhD. Oswin Deiva Stanley,
PhD. Rignolda Djamaluddin.

published by
Mangrove Action Project /
Yayasan Akar Rumpun Laut
April 2006 - Yogyakarta, Indonesia

with financial support from:
Working Assets
Global Greengrants
Zoological Society of London
Christensen Foundation
USAID - Environmental Service Program

This manual may be reproduced and cited
freely with the blessing of all creatures big
and small whose lives are entwined with the
fate of the mangroves.



i	introduction	2
	the five steps - about the manual - community involvement - restoration failures - key concepts - do your homework	

1	autecology	8
	pattern of mangrove reproduction - understanding local production - dispersal - understanding local dispersal - establishment and growth	

2	hydrology	15
	depth - duration and frequency - example of mangrove zonation	

3	disturbance	20
	stresses - determining stresses - case study - restoration options - taking measurements	




Table of Contents

Table of Contents



4	hydrological rehab design	31
	regarding substrate - tidal streams - tidal prisms - rehabilitation planning - poorly designed project - well designed projects - action taking	
5	planting	39
	assessing natural recruitment - planting considerations - mangrove nursery practices - broadcast of seedlings - planting holes - spacing and soil	
m	monitoring	47
s	summary	48
	advantages and disadvantages of natural regeneration - emerging restoration principles	
r	list of references	50



Introduction

Restoration and rehabilitation* of existing or former mangrove forest areas is extremely important today. In fact, given the importance of mangrove forest ecosystems, and the current threat to these coastal forests, this is an imperative. But actual planting of mangroves is rarely needed as mangroves annually produce hundreds or thousands of seeds or seedlings per tree, which under the proper hydrologic conditions can recolonize former mangrove areas (returned to normal hydrology) very rapidly.

There are many different techniques and methods utilized in restoring mangroves. Because some of these have resulted in identifiable successes or failures, we wish to present herein a summary description of several preferred methods for planning and implementing mangrove rehabilitation.

In summary, five critical steps are necessary to achieve successful mangrove restoration:


1. Understand the autecology (individual species ecology) of the mangrove species at the site; in particular the patterns of reproduction, propagule distribution, and successful seedling establishment.
2. Understand the normal hydrologic patterns that control the distribution and successful establishment and growth of targeted mangrove species.
3. Assess modifications of the original mangrove environment that currently prevent natural secondary succession (recovery after damage).
4. Design the restoration program to restore appropriate hydrology and, if possible, utilize natural volunteer mangrove propagule recruitment for plant establishment.
5. Only utilize actual planting of propagules, collected seedlings, or cultivated seedlings after determining (through steps a-d) that natural recruitment will not provide the quantity of successfully established seedlings, rate of stabilization, or rate of growth of saplings established as objectives for the restoration project (Lewis and Marshall 1997).

This manual provides an illustration of these five important steps, in order to make the methodology accessible to a wider range of coastal resource managers and mangrove restoration practitioners. It should be noted that this is not a comprehensive guide to mangrove restoration. For a fuller understanding and a more certain approach to restoration, the reader should research more thoroughly this subject, and consult more directly with those who are experienced experts in hands-on restoration techniques (see resources section at the end of this booklet). The techniques outlined herein are only a basic guide, and should be tailored to each unique situation and coastal region where restoration is being attempted.

It should also be made clear that **restoring** mangroves is only a partial solution. **Protection** of those precious remaining mangrove ecosystems must become an imperative for all nations, before too much is lost, and our restoration efforts are in vain.

- Mangrove Action Project Restoration Team, 2005

**The terms restoration and rehabilitation are used throughout this manual in the following way; The term "restoration" has been adopted to specifically mean any activity that aims to return system to a preexisting condition (whether or not this was pristine) (sensu Lewis 1990b), whereas the term "rehabilitation" is applied more generally and is used to denote any activity (including restoration and habitat creation) that aims to convert a degraded system to a stable alternative.*



Introduction

Involvement of the local community where mangrove rehabilitation is taking place is essential to the long term survival of the restored forest. This manual can not go into detail on the community organizing process, but will provide a few insights into ways that the community should be involved.

It may be best to think in terms of PAST, PRESENT and FUTURE when contemplating community involvement.

PAST - Why and how were the mangroves destroyed in the first place? What did the original mangrove forest look like? How did the community use the mangroves?



PRESENT - Who currently owns the land or has use rights to the land? Is the area currently productive? Who are the local actors interested in restoring the mangrove? What are the tidal levels of this region? Where does the water come from that feeds this mangrove area? How will we restore this mangrove area?


FUTURE - How will the community look after this mangrove once it is restored? What activities will be allowed/dis-allowed in the mangrove area? Who will enforce village regulations on mangrove protection and sustainable use? Is co-management with the government an option? How will you protect the mangroves from outside developers/investors?

Community Involvement

technical failures

There have been many failed restoration projects over the years, invariably wasting both time and money. One case study from North Sulawesi, Indonesia shows that the government planted the same disused shrimp pond area 5 times over a period of 8 years. Seedlings were planted without regard to ecological requirements (substrate height, water flow, appropriate species selection) and resultantly died within a year after each planting (below). Nonetheless project money was continually made available for re-planting without addressing the cause of the failure.

Introduction




seedlings planted without regard to substrate height, both in ditches and on dike walls.

social failures

In Kwandang Bay, Gorontalo Province, Indonesia the Forestry Department paid the village leader and seven of his family members 5 cents a piece to raise 60,000 seedlings, and promised another 5 cents for planting when the seedlings matured. The second payment never came, and the seedlings remain to this day, rooted in the nursery. The community at large was never involved in the project.

Restoration Failures



Introduction

“Ecological restoration” has been defined by the Society for Ecological Restoration (SER, 2002) as the “process of assisting the recovery of an ecosystem that has been degraded, damaged, or destroyed”.


Restoration or rehabilitation may be recommended when an ecosystem has been altered to such an extent that it can no longer self-correct or self-renew. Under such conditions, ecosystem homeostasis has been permanently stopped and the normal processes of secondary succession (Clements, 1929) or natural recovery from damage are inhibited in some way.

This manual is going to highlight the importance of assessing the existing hydrology of natural extant mangrove ecosystems, and applying this knowledge to first protect existing mangroves, and second to achieve successful and cost-effective ecological restoration if needed.

Key Concepts

Some homework is needed in advance of starting to plan a mangrove restoration project.

Introduction




Examples of things to look into might include reading tide tables and measuring tidal levels. Look for literature about the mangroves of your area and if possible their distribution and tidal requirements. Can you find any recent or even historical aerial photos? Has anyone ever tried to restore mangroves in your area? If so, what were their successes and failures? Were there any lessons learned from these previous efforts?

Things You May Need:

- Map of location (scale 1:25,000)
- Forestry management map (scale 1:5000)
- Land use map
- Tide tables from nearest port
- Survey equipment such as compass, rope, stakes, notebook, measuring tape, GPS unit.

Do Your Homework

AUTECOLOGY




Step One:

To understand the *autecology* (individual species ecology) of the mangrove species at the site, in particular the patterns of reproduction, propagule distribution, and successful seedling establishment.

Seedlings of selected viviparous mangrove species from Indonesia.


1) *Bruguiera gymnorhiza*; 2) *Rhizophora mucronata*; 3) *B. paviflora*;
4) *Avicennia marina* (a) newly germinated, (b) plumule elongating,
5) *Aegiceras corniculatum* (a) fruits, (b) single young fruit and (c) germinating fruit. From MacNae 1968.



After flowering and pollination, many mangroves develop viviparous seeds called *propagules*.

Vivipary is a characteristic in which the propagules develop early and germinate while still on the parent tree receiving food to keep the propagule healthy for a long time after they fall into the water. This enables the propagule to float with the tides until it comes to rest in a good place to grow.

The propagules then put down roots into the mud and use stored food to grow quickly into a young tree.





In order to understand the patterns of mangroves reproduction in your area, it will be useful to create a table similar to the table below.

Species	Type of Seed	Months	Indicator of Maturity	Size at Maturity
<i>Avicennia marina</i>	Propagule	D, *J , F	Yellow fruit skin	Weight of seed > 30 g
<i>Bruguiera gymnorhiza</i>	Propagule	M, J, J, A, S, O, N, D	Reddish brown body	length > 20 cm
<i>Ceriops tagal</i>	Propagule	A , S	Yellow collar, brown/ green body	length > 20 cm
<i>Rhizophora apiculata</i>	Propagule	D, J , M , A	Reddish collar	length > 20 cm, diameter > 14 mm
<i>Rhizophora mucronata</i>	Propagule	S, O, N, D	Yellow collar, green body	length > 50 cm
<i>Sonneratia alba</i>	Fruit	A, M , J, S , O	Float in water	fruit > 4 cm
<i>Xylocarpus granatum</i>	Fruit	S, O , N	Yellow/brown fruit Floats in Water	Weight of seeds inside fruit 30 g each


* Bold type indicates peak season

Adapted from Hachinohe et. AL, "Nursery Manual for Mangrove Species - At Benoa Port in Bali," JICA, 1998.

Like the coconut palm, mangroves have floating propagules. Because of their various shapes and sizes propagules of separate mangrove species float differently.




Small propagules such as *Avicennia* spp., *Aegiceras* spp. and small mangrove fruits such as *Sonneratia* spp. float far and wide on normal tidal currents. Because of their small size, these fruits and propagules easily reach new or disturbed areas and, if the soil conditions are right, become quickly established. These species are known as *colonizers*.





Large propagules such as *Rhizophora* spp. and large mangrove fruits such as *Xylocarpus* spp. are not as easily dispersed as smaller fruits and propagules. The larger propagules may have difficulty entering into areas where normal tidal exchange has been blocked such as is often the case in disused shrimp ponds





Before addressing local issues concerning hydrology (Step Two), it will be useful to understand local mangrove seedling dispersal. Completing the table below will help you understand the availability of local seeds/propagules.

Species	Season	Distance from rehab site to seed source	*Presence/absence of propagules in rehab area	
<i>Avicennia marina</i>	D, J, F	< 1km, 1-5 km, >5km	Yes ☒	No ☐
<i>Bruguiera gymnorhiza</i>	May - Dec	< 1km, 1-5 km, <5km	Yes ☐	No ☒
<i>Ceriops tagal</i>	A, S	< 1km, 1-5 km, >5km	Yes ☒	No ☐
<i>Rhizophora apiculata</i>	D, J, M, A	< 1km, 1-5 km, <5km	Yes ☐	No ☒
<i>Rhizophora mucronata</i>	S, O, N, D	≤ 1km, 1-5 km, >5km	Yes ☐	No ☒
<i>Sonneratia alba</i>	A, M, J, S, O	< 1km, 1-5 km, >5km	Yes ☒	No ☐
<i>Xylocarpus granatum</i>	S, O, N	< 1km, 1-5 km, <5km	Yes ☐	No ☒
Other				
Other				

* Includes seeds/propagules (rooted, alive or dead) in the rehab area, or stranded on a barrier such as a dike wall just outside of the area.

Mangroves often occur in zones, which are groupings of the same species of mangrove within a whole mangrove forest. Zonation occurs because different species of mangrove need particular conditions to grow. Some species require more water than others. Some species are able to tolerate more saline soils than others. The species occurring in a zone depends on:


- a) depth, duration and frequency of tidal inundation
- b) soil salinity
- c) amount of fresh water available



2 HYDROLOGY

Step Two:

Understand the normal hydrologic patterns that control the distribution and successful establishment and growth of targeted mangrove species.





Distribution and establishment of *Sonneratia littoralis*

The single most important factor in designing a successful mangrove restoration project is determining the normal hydrology (depth, duration and frequency of tidal inundation, and of tidal flooding) of existing natural mangrove plant communities (a reference site) in the area you wish to restore.

Water Depth/ Substrate Height

Table 3 - Changes of Tide Height Level at Benoa Port in Bali



☒ Each mangrove species thrives at a different substrate level which in some part dictates the amount of exposure the mangrove will have to tidal waters. For instance most *Avicennia* species thrive at lower substrate levels (deeper water) while *Heritrea* sp. thrive inland at higher substrate levels (shallower water)

☒ You will need to study tide charts for your area and begin to take measurements in healthy mangroves relating substrate height/depth to the various species of mangroves that exist at each depth.

☒ When it comes time to rehabilitate a destroyed mangrove area, one of the keys is going to be to imitate the slope and topography (relative height) of the substrate from a nearby healthy mangrove forest.

Frequency of Inundation

It will be essential to note the critical periods of inundation and dryness that govern the health of the forest.

Among the most widely used approaches for mangrove zonation is the following scheme based on degree and frequency of tidal inundation developed by Watson (1928) from his work on Malayan mangroves.

Class	Flooded By	Height above chart datum in feet (meters)	Flooding Frequency (times/month)
1	All high tides	0-8 (2.44)	56-62
2	Medium high tides	8-11 (3.35)	45-59
3	Normal high tides	11-13 (3.96)	20-45
4	Spring high tides	13-15 (4.57)	2-20
5	Abnormal (equinoctial tides*)	15	2

**Equinoctial tides are extremely high or low tides which occur twice a year around March 21 and September 23.*

An example of how Watson's inundation classes can be applied may help to clarify things. Below Watson's "Inundation Classes" are applied to the mangroves of Indonesia.

Class 1: Mangroves in this class are inundated by all high tides. Predominant species found in these environments are *Rhizophora mucronata*, *R. stylosa* and *R. apiculata*. *R. mucronata* prefers areas under greater freshwater influence. In East Indonesia pioneering *Avicennia* and *Sonneratia* forests may dominate this zone.


Class 2: Mangroves in this class are inundated by all medium-high tides. Predominant species are *Avicennia alba*, *A. marina*, *Sonneratia alba* and *R. mucronata*.

Class 3: Inundation by normal high tides. Most species thrive under these conditions. A large part of the mangrove ecosystem falls into this class which exhibits the highest biodiversity of mangroves. Common species are *Rhizophora* spp. (often dominates), *Ceriops tagal*, *Xylocarpus granatum*, *Lumnitzera littorea* and *Exoecaria agallocha*.

Class 4: Inundation only during spring tides. Area generally too dry for *Rhizophora* spp., but it may be present in low numbers. Common species are *Bruguiera* spp., *Xylocarpus* spp., *Lumnitzera littorea* and *Exoecaria agallocha*.

Class 5: Inundation only during equinoctial or other exceptionally high tides. Predominant species are *Bruguiera gymnorrhiza* (dominates), *Instia bijuga*, *Nypa fruticans*, *Herritera littoralis*, *Exoecaria agallocha*, and *Aegiceras* spp.

Creating a similar figure like the one below appropriate to your region will become a construction model for your rehab project.



Mangrove zonation related to tidal datums in Sumatera, Indonesia
(modified from Whitten et al., 1987)

Example of Mangrove Zonation


DISTURBANCE

Step Three:

Assess modifications of the original mangrove environment that currently prevent natural secondary succession.



Restoration
planning should first
look at the potential existence of
stresses such as blocked tidal
inundation that might prevent
secondary succession from
occurring, and plan on
removing that stress
before attempting
restoration.



Disturbance

3

It is important to understand the past use of the area. First and foremost was the area intended for restoration actually a mangrove area in the past. Oftentimes, mangroves are planted in areas such as mud flats, salt marshes, or lagoons assuming that the area would be better off or more productive as a mangrove forest. But mud flats have their own ecological purposes such as a feeding grounds for migratory shorebirds.

A Department of Forestry program in Thailand unsuccessfully planted mangroves twice in an area of salt pans, apparently not learning from their mistakes.



Determining Stresses

Many times; however, human activities have damaged or destroyed mangrove ecosystems. Disused shrimp ponds, clear-cut mangrove areas for charcoal production, or mangroves which are drying out as a result of nearby changes in hydrology (due to construction of dikes, levees, roads, upland deforestation) are all areas where mangrove rehabilitation may be attempted. In these cases, before planting mangroves or attempting another type of restoration it is imperative to determine if the area is presently suitable for mangrove growth. If not, what are the stresses preventing growth of mangroves? Work together with the local community to help determine how the mangrove area has changed over time and why.


Disturbance

3

Examples of Stresses:

- ◆ Lack of groundwater
- ◆ Blockage of tidal exchange
- ◆ Hypersaline or acid sulfate soils
(usually after intensive shrimp farming)
- ◆ Overgrazing by goats, camels etc.
- ◆ Shoreline abrasion and lowered substrate level

The disused shrimp ponds in the following case study were replanted by local and regional government five (5) times unsuccessfully without addressing the root causes of why mangroves did not grow in that area. This “project-oriented” mindset, planting for the sake of spending available budget is also a form of stress that has to be overcome.



Determining Stresses

Disturbance



Case Study: This 20 hectare shrimp pond complex in Tiwoho, North Sulawesi was in operation for a period of 6 months during 1991. After abandonment the dike wall nearest to the sea degraded due to stronger wave action. Natural mangrove revegetation took place within the 5 seaward ponds. A density of 2500 seedlings per hectare was measured in 2000, with some trees nearly 10 meters tall


The five leeward ponds have experienced little to no natural regrowth due to the presence of intact dike walls and deep channels robbing the landward mangroves of regular tidal inundation.

Case Study

The map to the left depicts the same disused shrimp pond complex from Tiwoho, North Sulawesi.

Illustrated are natural inflows and outflows of tidal and fresh water (numbered 1-4) as well as disturbances to normal tidal inundation. In this case the disturbances are both intact and partially intact dike walls as well as artificial tidal channels or troughs.

The dike walls obviously disturb tidal inundation by blocking the natural entry and exit of tidal waters. The artificially low elevation of the troughs rob the areas within the shrimp ponds of tidal waters during times of the month when tidal fluctuations are minimal.





Disturbance

3


Options for restoration of aquaculture ponds include...

a) Simply restoring hydrologic connections to impounded mangroves. Breaching dikes and filling/blocking ditches.



b) The construction, by excavation of fill or back-filling of an excavated area, to create a target restoration site with the same general slope, and the exact tidal elevations relative to a benchmark as the reference site, thus insuring that the hydrology is correct.

Restoration Options



Measure the average substrate height in a nearby healthy mangrove during a known tidal level and then again during the same tidal level at your mangrove rehabilitation site to determine a suitable substrate level as your target for hydrological restoration.

Taking Measurements

Disturbance




3

Survey Techniques

You may wish to employ topographic survey techniques to assist you in determining relative substrate elevation.

Two main types of survey techniques are:

- A) Use of surveyor's equipment; levels, transits, theodolites
- B) Use of a water level; rubber tubing, water and meter sticks. (low-tech method below)



How to Make and Use A Bucket and Hose Water Level

Material Requirements

You will need a standard plastic bucket and 12 metres (40 ft.) of 6 mm (1/4") nylax clear plastic tube or similar. Both items can be purchased from any major building suppliers.

Instructions

1. Drill a hole in the bucket 50 mm (2") up from the bottom. The hole size should be slightly smaller than the plastic tube.
2. Slice one end of the plastic tube about 50 mm (2") down. Fig 1 This enables the tube to be threaded into the slightly smaller hole in the bucket. Fig 2
3. Pull the tube from the inside of the bucket until tight. Fig 3

Taking Measurements

Method A: This method is good for determining a *Datum Line* which can be used as a reference height when re-creating a sloped substrate. A “datum” is just a convenient reference point for other elevation measurements. It is usually given the designation “O”, and thus an elevation 30 cm higher than the datum would correctly be called +30cm relative to the datum. In some areas “surveyed datums” exist and can be found and referenced. A marker is usually placed to use as a reference point.

Disturbance

3

Place the bucket on a chair and fill to the top with water. The height of the bucket does not matter.

Let the hose loose on the ground until water is running out freely and all the air bubbles have come through.

Pick up the end of the hose and hold it against Post (1).


Mark the post where the water line shows in the hose. This becomes the datum line (not the known required height).

Mark the datum height on post (2), and post (3) in the same way. You now have a level datum line on all three objects.

You do not need the water level any more.

To re-create a sloped substrate, simply measure up or down from the datum height marked on each post.

For instance if datum height is the Mean Sea Level, you may want to mark 5 cm above the datum line on post (1), 5 cm below the datum line on post (2), and 15 cm below the datum line on post (3) to create a slope that drops 10 cm between each post.



Taking Measurements


Disturbance

3

Method B: This method is good for determining heights compared with a known benchmark in shrimp ponds, ditches, or in the mangrove forest.

- Pick up the end of the hose and hold it against a piece of rod held up right on area (X).
- Mark a pencil line on the rod where the water line shows in the hose.
- Walk down the hill and do the same over area (Y).

- You will now have two pencil marks on the rod. Whatever the distance measures between the two marks, is also the distance area (X) will need to be dug down to be level with area (Y).



For more information on how to make and use a water level see;

www.buideazy.com/fp_waterlevel.html or

<http://www.factsfacts.com/MyHomeRepair/WaterLevel.htm>

Taking Measurements


Hydro Rehab Design

Step Four:

Design the restoration program to restore appropriate hydrology and, if possible, utilize natural volunteer mangrove propagule recruitment for plant establishment.




Hydro Rehab Design




One basic theory behind hydrological rehabilitation is to recreate a natural slope and substrate height which will support normal tidal flow, and the natural re-establishment and growth of mangrove seedlings.

Dike walls of disused shrimp ponds need to be levelled, and ditches need to be filled. If you can not level dike walls entirely, opening strategic breaches may be enough to support the exchange of tidal waters and should lead to further degradation of the dike walls over time.



Regrading Substrate



Tidal streams run through mangrove areas from the terrestrial edge to the sea. They are narrower upstream, widening as they meander to the coast.


Tidal streams are fed from the landward edge by ground water, springs, runoff and streams. Because they are connected to the sea, tidal streams facilitate the exchange of tidal waters in and out of the mangrove area.

When tidal streams are disturbed, a mangrove may dry out, and die over time.


Hydro Rehab Design

The arrow in the diagram at right indicates the historical flow of the natural tidal stream.

The hashed lines indicate the path of the desired tidal stream.




In the case of rehabilitating disused shrimp ponds, it may be enough to create “strategic breaches” in the dike walls. In this case, less rather than more cuts in dikes is better. The reason is that the *tidal prism* (the amount of water that can enter an opened pond between high and low tide) needs to be channeled to the extent possible through a few key openings that are wider downstream than upstream. This mimics the normal operation of tidal streams in mangroves (see previous page). Fewer openings produce greater velocities as the flow is restricted, which in turn produces scouring, which keeps the human-made openings open and reduces the chances of siltation and closure. Too many openings distribute the tidal prism over many points, reduces the velocity, and induces less scour and more siltation.



A) Breaching of dikes without proper hydrological design.

B) Creation of a straight, unnatural looking canal.


Poorly Designed Project



Do It Right! Connect the ponds with the sea by creating well designed tidal channels. Note the channels meander and widen as they flow toward the sea.

Well Designed Project

Fill in the ditches and breach the dike walls with...



Hydro Rehab Design

4

This "x" indicates strategic positions to breach dike walls in order to mimic the flow of a historical tidal stream through the mangroves. These natural tidal streams within the mangrove are more narrow at the landward edge spreading outward as they flow to the sea



This figure indicates where ditches or artificial tidal channels need to be filled.



Hydro Rehab Design

4

Now it is time to act upon your rehabilitation plan. If you don't have financial resources for or access to heavy equipment, you may need to recruit community volunteers, university students or ask for help from the government.

Remember, you might not need to re-grade the entire rehabilitation area, strategically breaching the dikes to enhance tidal exchange and filling deep channels may suffice.



...implement the rehab plan!

...take action!

Mangrove Planting



Step Five:

Only utilize actual *planting* of propagules, collected seedlings, or cultivated seedlings after determining (through steps a-d) that natural recruitment will not provide the quantity of successfully established seedlings, rate of stabilization, or rate of growth of saplings established as objectives for the restoration project.

Mangrove Planting

5

Determine by observation if natural seedling recruitment is occurring once the stress has been removed. This means monitoring. Are seedlings coming into the area? Are they taking root? What is the density of seedlings per hectare? You will probably want a minimum of 1000 seedlings per hectare with 2500 seedlings per hectare as a good figure. How are they growing? Have they survived the dry season?

Note: Even if mangroves survive for several years in your rehab area they may remain stunted or even die out unless hydrological conditions are truly supportive of mangrove growth.


If seedlings have established in the rehabilitation area, but at lower densities than hoped for, you may consider planting. But planting costs can double the overall cost of a project and may limit the biodiversity of the site due to competition from planted mangroves (usually only one or two species) with volunteer species (5-15 species).

If no seedlings have established in the area, even though a natural seed source is nearby, you will have to re-evaluate the effectiveness of your hydrological rehabilitation. Perhaps there are still blockages to normal tidal flow or there is a disturbance in the seed source.



There already exist some excellent guides to planting mangroves, which we listed in the resources section at the end of this booklet.

We have provided some tips nonetheless based on our experiences planting mangroves.



Seed Stock - There are four sources of seeds/propagule for mangrove planting;

- ▲ Raising seedlings in a nursery from local seed sources
- ▲ Direct planting of propagules
- ▲ Transplanting of wild seedlings
- ▲ Broadcast fruits/propagules directly on the water surface during incoming tides.

The following table gives a synopsis of the nursery method for various seedlings. For more information see the JICA Manual "Nursery Method for Mangroves."

Species	Type of Seed	Months of Seed Collection	Indicators of Maturity	Seed Selection	Seed Storage (max # days)
<i>R. mucronata</i>	Viviparous	S,O,N,D	Yellow cotyledon, green hypocotyl	Length of hypocotyl > 50 cm	10
<i>R. apiculata</i>	Viviparous	D,J,F,M,A	Reddish cotyledon	Length of hypocotyl > 20 cm Diameter: > 14mm	5
<i>B. gymnorrhiza</i>	Viviparous	M,J,J,A,S,O,N,D	Reddish brown or greenish red hypocotyl	Length of hypocotyl > 20 cm	10
<i>C. tagal</i>	Viviparous	A,S	Yellow cotyledon, Brownish green hypocotyl	Length of hypocotyl > 20 cm	10
<i>S. alba</i>	Normal	A,M,J, & S,O	Float in water	Fruit > 40 mm	5
<i>A. marina</i>	Crypto-viviparous	D,J,F	Yellowish fruit skin	Weight of seeds > 1.5 g	10
<i>X. granatum</i>	Normal	S,O,N	Wellow to brown fruit, Float in water	Weight of seeds > 30 g	10

Hachinhoe, Hideki et. Al., "Nursery Manual for Mangrove Species - At Benoa Port in Bali"
Ministry of Forestry and Estate Crops, Indonesia & Japan International Cooperation Agency (1998)

Summary of Nursery Practices Continued

Species	Sowing	Shading	Watering	Pest Control	Remarks
<i>R. mucronata</i>	Push $\pm$ 7 cm into soil surface	50% 2/3 of sides	at neap tide	insects caterpillars	
<i>R. apiculata</i>	Push $\pm$ 5 cm into soil surface	50% 2/3 of sides	at neap tide	-	
<i>B. gymnorrhiza</i>	Push $\pm$ 5 cm into soil surface	30% 2/3 of sides	at neap tide	-	Don't forcefully remove calyx
<i>C. tagal</i>	Push $\pm$ 5 cm into soil surface	50% 2/3 of sides	at neap tide	-	
<i>S. alba</i>	Push radicle lightly into soil surface	30% whole sides	twice a day	rats, crabs caterpillars	Use wire mesh to keep seed in place, add 30% cow dung to soil.
<i>A. marina</i>	Lay on surface	30% whole sides	fully once a day	crabs caterpillars	
<i>X. granatum</i>	Lay on surface, radicle downward	30% whole sides	fully once a day	crabs	

Hachinhoe, Hideki et. Al., "Nursery Manual for Mangrove Species - At Benoa Port in Bali"
Ministry of Forestry and Estate Crops, Indonesia & Japan International Cooperation Agency (1998)

Mangrove Planting

TIPS FOR PLANTING MANGROVES

The collection and distribution by hand onto the water's surface of seeds or seedlings from natural collection areas stimulates natural re-growth of mangroves. Propagules and seeds suitable for collection are commonly found along high tide lines. If an area lacks natural seed sources, seeds may be collected from another area that has a lot of seeds, transported to the restoration site, and as the tide turns and flows into the restoration site, the seeds are broadcast onto the water and allowed to float and find their own suitable location for germination. It is a good idea to do this on a series of different tides, like the neap, the spring, and several in between during the month of maximum availability of the seeds.



Broadcast of Seedlings


TIPS FOR PLANTING MANGROVES

Mangrove Planting

5

Avoid "J"-Roots

When placing the seedling in the prepared hole it is good for one person to hold the seedling so that the top of the root ball is even with the surface of the soil. It is also important that the roots be allowed to dangle freely, straight into the hole. Roots in contact with the bottom of the hole will curl upward (like the letter "J") which may stunt growth or even kill the plant.




Hole Size

The prepared hole for planting should be 1.5 times wider and 1.5 times deeper than the root ball of the seedling.

Loose Soil

It is common for people to stomp on the soil surface after planting a seedling. Compacting the soil in this way eliminates small air pockets needed by the roots. It is best to lightly back-fill soil into the hole so that the hole is completely filled with loose soil. Save the stomping for the dance floor!




Planting Holes

TIPS FOR PLANTING MANGROVES

No soil amendments

Except in the case of planting *Sonneratia* spp., do not add compost or fertilizer when planting mangrove seedlings. Addition of fertilizer discourages the roots from spreading to find their own nutrients



2-meter spacing - random planting.

Mangroves do not naturally grow in straight rows! Why plant them in straight rows?

Planting in straight rows can result in artificial channelization between the rows which will rob water from the mangroves.



Activities	Remarks
Monitor mangrove species that develop	Check correctness of original provenance of propagules and seed
Monitor growth as a function of time	Parameters include the density, percent cover and species composition of both planted and volunteer mangroves over time.
Monitor growth characteristics	Include determination of stem structure, node production, phenology, fruiting and resistance to pests
Record level of failure of saplings	Provide a scientific explanation of failure
Record levels of rubbish accumulation	Note source of rubbish and steps taken to minimize the problem
Adjust density of seedlings and saplings to an optimum level	Degree of thinning, replanting or natural regeneration should be noted. Growth should be monitored
Estimate cost of restoration project	The estimation of costs should include all the undertakings including site preparation, propagule collection, nursery establishment, field transplantation, etc.
Monitor impact of any harvesting project	This should be part of any long-term record for restoration
Monitor characteristics of the rehabilitated mangrove ecosystem	This involves detailed measurement of fauna, flora and physical environment of the new mangrove ecosystem and comparison with similar undisturbed mangrove ecosystems.

Summary


Advantages and disadvantages of natural regeneration

Advantages:

- + Cheaper to establish,
- + Less subsidy is needed in terms of labour and machinery,
- + Less soil disturbance,
- + Saplings establish more vigorously,
- + Origin of seed sources usually known.
- + Nature will plant the mangroves species in the correct tidal zones. Only those mangroves in the correct zone will survive through competition.

Disadvantages:

- Replacement may not be of the same species removed,
- Absence of mother trees may result in low/or no propagules supply,
- Genetically improved stock not easily introduced,
- Excessive wave action may cause poor establishment,
- Predation of propagules by macro benthos (e.g. crabs, snails etc),
- Less control over spacing, initial stocking and composition of seedlings.



Emerging Restoration Principles

Summary



- ⊆ Get the hydrology right first!
- ⊆ Do not build a nursery, grow mangroves and just plant some area currently devoid of mangroves (like a convenient mud flat). There is a reason why mangroves are not already there or were not there in the recent past or have disappeared recently. Find out why.
- ⊆ Once you find out why, see if you can correct the conditions that currently prevent natural colonization of the selected mangrove restoration site. If you cannot correct those conditions, pick another site.
- ⊆ Use a reference mangrove site for examining normal hydrology for mangroves in your particular area. Either install tide gauges and measure the tidal hydrology of a reference mangrove forest or use the surveyed elevation of a reference mangrove forest floor as a surrogate for hydrology, and establish those same range of elevations at your restoration site or restore the same hydrology to an impounded mangrove by breaching the dikes in the right places. The “right places” are usually the mouths of historic tidal creeks. These are often visible in vertical (preferred) or oblique aerial photographs.
- ⊆ Remember that mangrove forests do not have flat floors. There are subtle topographic changes that control tidal flooding depth, duration and frequency. Understand the normal topography of your reference forest before attempting to restore another area.

List of References - General

Bengen, Dr. Dietrich G., "Pengenalalan dan Pengelolaan Ekosistem Mangrove," Pusat Kajian Sumberdaya Pesisir dan Lautan - Bogor Institute of Agriculture, 2000

Duke, N. 1996. Mangrove restoration in Panama. pp. 209-232 In C. Field (ed.) Restoration of Mangrove Ecosystems. International Society for Mangrove Ecosystems, Okinawa, Japan. 250 pp.

Drs. Duong Quang Dieu, Phan Nguyen Hong, et al, "Mangroves Are Easy To Plant, But Much Profitable", an educational comic by MERC, Vietnam National University, Hanoi, Apr. 1995

Hachinohe, Hideli et. Al., "Nursery Manual for Mangrove Species at Benoa Port in Bali," JICA & Ministry of Forestry and Estate Crops, Indonesia. 1998

Hamilton, L. S. and S.C. Snedaker (eds.). 1984. Handbook of mangrove area management. East West Centre, Honolulu, Hawaii, USA. 123 pp.

IIRR, IDRC, FAO, NACA and ICLARM. "Utilizing Different Aquatic Resources for Livelihoods in Asia: A Resource Book." 2001 Philippines 416 pp.

Keeley, Martin A., "Marvelous Mangroves in the Cayman Islands, A Curriculum-Based Teachers' Resource Guide." West Indian Whistling-Duck Working Group, Society of Caribbean Ornithology. 2001

Kitamura, Shozo, et Al., "Handbook of Mangroves in Indonesia," JICA & ISME. 1997

List of References - General

Liyanage, PhD Sunil, "Planting Manual for the Mangroves of Sri Lanka," MAP-SFFL Mangrove Resource Center - Small Fishers Federation of Lanka. 2000

Melana, Dioscoro M. et. Al, "Mangrove Management Handbook," CRMP Document No. 15-CRM/2000, Manilla Philippines

Molony, Brett & Marcus Stevens, "Mangroves, Ecology of Intertidal Forests" UNESCO Tropical Marine Studies: 4. 1995

Primavera, Jurgenne H., et Al., "Handbook of Mangroves in the Philippines Panay," SEAFDEC 2004

Soemodihardjo, S., P. Wiroatmodjo, F. Mulia, and M.K. Harahap. 1996. Mangroves in Indonesia - a case study of Tembilahan, Sumatra. pp. 97-110 In C. Fields (ed.) Restoration of Mangrove Ecosystems. International Society for Mangrove Ecosystems, Okinawa, Japan. 250 pp.

Taniguchi Keisuke et. Al., "Mangrove Silviculture" JICA & Ministry of Forestry and Estate Crops, Indonesia. 1999

Talbot, Frank & Clive Wilkinson, "Coral Reefs, Mangroves and Seagrasses, A Sourcebook for Managers," AIMS. 2001

Tomlinson, P.B., "The Botany of Mangroves," Cambridge University Press. 1986.

List of References - Hydrological Restoration Papers

Stevenson, N.J. , R.R. Lewis, and P.R. Burbridge, "Disused Shrimp Ponds and Mangrove Rehabilitation." Wetlands International-Africa, Europe and Middle East, PO Box 7002, Droevendaalsesteeg, 3a, 6700 CA, Wageningen, Nederland.

Lewis, R. R. and Marshall, M. J. (1997). "Principles of Successful Restoration of Shrimp Aquaculture Ponds Back to Mangrove Forests." Programa/resumes de Marcuba '97, September 15/20, Palacio de Convenciones de La Habana, Cuba. 126.

Lewis, R. R., "Restoration of Mangrove Habitat," ERDC TN-WRP-VN-RS-3.2, October 2000

Lewis, R. R., "Ecological Engineering for Successful Management and Restoration of Mangrove Forests," Ecological Engineering 24 (2005) 403–418

For more information on ecological/hydrological mangrove rehabilitation see:
www.mangroverestoration.com

For Further Information or Consultation

Dr. Phan Nguyen Hong at CRES, Hanoi National Pedagogic University, 91 Nguyen Khuyen Str., Hanoi, Vietnam, fax 84-4256562

Motohiko Kogo, Chairman, Action For Mangrove Reforestation, 3-29-15-1104 Honcho, Nakano, Tokyo 164, Japan, extensive mangrove replanting work

Prof. Dr. Peter Saenger, Head of the Centre for Coastal Management, Southern Cross University, P.O. Box 157, Lismore NSW 2480, Australia, fax 61-66-212669

Roy R. "Robin" Lewis III, President, Lewis Environmental Services, Inc., P.O. Box 400, Apollo Beach, FL, USA 33572. Email: LESrl3@aol.com Consultant and expert on mangrove restoration in Florida, Mexico, Cuba, US Virgin Islands, Nigeria, Thailand, Vietnam and Hong Kong.

Psit Chansnoh, President of Yad Fon Association, 16/8 Rakchan Road, Amphur Muang, Trang-92000, Thailand, fax 66-75-219327 yadfon@loxinfo.co.th, expert on community involvement

Dr. J.H. Primavera, Southeast Asian Fisheries Development Center (SEAFDEC), Aquaculture Dept., P.O. Box 256, Iloilo City, Philippines, fax 63-33-81340

Dr. Samuel Snedakar , University of Miami, Rosentell ssnedakar@rsmas.miami.edu School of Marine Sciences world renowned mangrove expert

